

ESTIMATED INSTALLATION TIMES



The following chart outlines Tommy Gate estimated liftgate installation times by Series and Vehicle Application.

Please note that some installations may take more or less time than estimated. If a liftgate is ordered with a T-64 light kit, a T-54 light kit, or in-frame lights, allow an extra hour for installation time.

| APPLICATION | HOURS TO INSTALL |
|--|------------------|
| G2 SERIES & ORIGINAL SERIES | |
| Pickup (500, 1000, 1300, & 1500 lbs.) | 4.5 hours |
| Service & Utility Body (1000, 1300, & 1600 lbs.) | 4.5 hours |
| Flatbed, Stake, & Van (1000,1300, & 1600 lbs.) | 6-8 hours |
| Lift N' Dump (1600 lbs.) | 6-8 hours |
| Cargo Van (1000lbs.) | 7-8 hours |
| TUCKUNDER SERIES | |
| TKT Models | 12 hours |
| TKL Models | 12 hours |
| RAILGATE SERIES | |
| Flatbed, Stake, & Van (1600 & 2000 lbs.) | 8 hours |
| Flatbed, Stake, & Van (2500 & 3000 lbs.) | 8 hours |
| CANTILEVER SERIES | |
| Cargo Van (1300 lbs.) | 12 hours |
| 650 SERIES | |
| Cargo Van (650 lbs.) | 8 hours |
| V2 SERIES | |
| Cargo Van (1100 lbs.) | 6 hours |
| Flatbed, Stake, & Van (1100 lbs.) | 6 hours |